

TABLE 1 – ASBESTOS SAMPLING RESULTS

Woodstock Library
Spectrum Project # 21-131

Date Sampled: January 28 & 29, 2021

Sample #	Description	Location/Area	PLM Results (% Type)	TEM Results (% Type)
01	Floor tile adhesive	Main floor throughout	NAD	NAD
02	Floor tile adhesive	West addition floor throughout	NAD	NAD
03	12x12 floor tile (Beige)	Main floor throughout	NAD	NAD
04	12x12 floor tile (Beige)	West addition floor throughout	NAD	NAD
05	Brown 12x12 floor tile & adhesive	Librarians Office Kitchenette	NAD	NAD
06	Brown 12x12 floor tile & adhesive	Librarians Office Kitchenette	NAD	NAD
07L1	Off White 12x12 floor tile & adhesive (Tile)	Librarians Office	NAD	NAD
07L2	Off White 12x12 floor tile & adhesive (Adhesive)	Librarians Office	NAD	NAD
08L1	Off White 12x12 floor tile & adhesive (Tile)	Librarians Office	NAD	NAD
08L2	Off White 12x12 floor tile & adhesive (Adhesive)	Librarians Office	NAD	NAD
09	Beige 12x12 floor tile	Public bathroom foyer	NAD	NAD
10	Beige 12x12 floor tile	Public bathroom foyer	NAD	NAD
11	Floor covering adhesive	2nd floor throughout	Chrysotile 12.9%	NA
12	Floor covering adhesive	2nd floor throughout	N/A/PS	NA
13	Speckled floor covering	2nd floor throughout	NAD	NAD
14	Speckled floor covering	2nd floor throughout	NAD	NAD

Note: Asbestos containing materials are greater than 1% asbestos. Trace is considered less than 1% asbestos.
NAD - no asbestos detected, NA - not applicable, PS – Positive Stop, SF - square feet, LF – linear feet

TABLE I – ASBESTOS SAMPLING RESULTS

Woodstock Library
Spectrum Project # 21-131

Date Sampled: January 28 & 29, 2021

Sample #	Description	Location/Area	PLM Results (% Type)	TEM Results (% Type)
15	Pink 12x12 floor tile	Janitors closet	NAD	NAD
16	Pink 12x12 floor tile	Janitors closet	NAD	NAD
17	Textured ceiling plaster	Art room	Chrysotile 7.5%	NA
18	Textured ceiling plaster	Art room	NA/PS	NA
19	Textured ceiling plaster	Children's library	NA/PS	NA
20	Textured ceiling plaster	Children's library	NA/PS	NA
21	Textured ceiling plaster	West addition	NA/PS	NA
22	Glue Dabs	Main library area ceiling	NAD	NAD
23	Glue Dabs	Main library area ceiling	NAD	NAD
24	12 x 12 Ceiling tile	Main library area ceiling	NAD	NAD
25	12 x 12 Ceiling tile	Main library area ceiling	NAD	NAD
26	Plaster – skim coat	Main library area ceiling	NAD	NA
27	Plaster – skim coat	Walls throughout	NAD	NA
28	Plaster – skim coat	Walls throughout	NAD	NA
29	Plaster – skim coat	Ceiling throughout	NAD	NA
30	Plaster – skim coat	Ceiling throughout	NAD	NA

Note: Asbestos containing materials are greater than 1% asbestos. Trace is considered less than 1% asbestos.
NAD - no asbestos detected, NA - not applicable, PS – Positive Stop, SF - square feet, LF – linear feet

TABLE 1 – ASBESTOS SAMPLING RESULTS

Woodstock Library
Spectrum Project # 21-131

Date Sampled: January 28 & 29, 2021

Sample #	Description	Location/Area	PLM Results (% Type)	TEM Results (% Type)
31	Base coat plaster	Walls throughout	NAD	NA
32	Base coat plaster	Walls throughout	NAD	NA
33	Base coat plaster	Walls throughout	NAD	NA
34	Base coat plaster	Ceiling throughout	NAD	NA
35	Base coat plaster	Ceiling throughout	NAD	NA
36	Joint compound	Walls throughout	NAD	NA
37	Joint compound	Ceiling throughout	NAD	NA
38	Sheetrock	Walls throughout	NAD	NA
39	Sheetrock	Ceiling throughout	NAD	NA
40	Tar paper	Vapor barrier bottom layer roof 1 main roof	NAD	NAD
41	Tar paper	Vapor barrier bottom layer roof 1 main roof	NAD	NAD
42	Shingle	Mid layer roof 1 main roof	NAD	NAD
43	Shingle	Mid layer roof 1 main roof	NAD	NAD
44	Shingle	Top layer roof 1 main roof	NAD	NAD
45	Shingle	Top layer roof 1 main roof	NAD	NAD
46	Silver coating	Flat roof off roof 1 main roof	NAD	NAD

Note: Asbestos containing materials are greater than 1% asbestos. Trace is considered less than 1% asbestos.
NAD - no asbestos detected, NA - not applicable, PS – Positive Stop, SF - square feet, LF – linear feet

TABLE 1 – ASBESTOS SAMPLING RESULTS

Woodstock Library
Spectrum Project # 21-131

Date Sampled: January 28 & 29, 2021

Sample #	Description	Location/Area	PLM Results (% Type)	TEM Results (% Type)
47	Silver coating	Flat roof off roof 1 main roof	NAD	NAD
48	Tar paper	Vapor barrier bottom layer roof 2	NAD	NAD
49	Tar paper	Vapor barrier bottom layer roof 2	NAD	NAD
50	Shingle	Top layer roof 2	NAD	NAD
51	Shingle	Top layer roof 2	NAD	NAD
52	Tar paper	Vapor barrier bottom layer roof 3	NAD	NAD
53	Tar paper	Vapor barrier bottom layer roof 3	NA	NA
54	Shingle	Mid layer roof 3	NAD	NAD
55	Shingle	Mid layer roof 3	NAD	NAD
56	Shingle	Top layer roof 3	NAD	NAD
57	Shingle	Top layer roof 3	NAD	NAD
58	Tar paper	Vapor barrier bottom layer roof 4	NAD	NAD
59	Tar paper	Vapor barrier bottom layer roof 4	NAD	NAD
60	Shingle	Top layer roof 4	NAD	NAD
61	Shingle	Top layer roof 4	NAD	NAD
62	Tar paper	Vapor barrier bottom layer roof 5	NAD	NAD

Note: Asbestos containing materials are greater than 1% asbestos. Trace is considered less than 1% asbestos.
NAD - no asbestos detected, NA - not applicable, PS – Positive Stop, SF - square feet, LF – linear feet

TABLE 1 – ASBESTOS SAMPLING RESULTS

Woodstock Library
Spectrum Project # 21-131

Date Sampled: January 28 & 29, 2021

Sample #	Description	Location/Area	PLM Results (% Type)	TEM Results (% Type)
63	Tar paper	Vapor barrier bottom layer roof 5	NAD	NAD
64	Shingle	Top layer roof 5	NAD	NAD
65	Shingle	Top layer roof 5	NAD	NAD
66	Tar paper	Vapor barrier bottom layer roof 6	NA	NA
67	Tar paper	Vapor barrier bottom layer roof 6	NAD	NAD
68	Shingle	Mid layer roof 6	NAD	NAD
69	Shingle	Mid layer roof 6	NAD	NAD
70	Shingle	Top layer roof 6	NAD	NAD
71	Shingle	Top layer roof 6	NAD	NAD
72	Flashing	Shed roof connecting roof 4 & roof 5	NAD	NAD
73	Flashing	Shed roof connecting roof 4 & roof 5	NAD	NAD

Note: Asbestos containing materials are greater than 1% asbestos. Trace is considered less than 1% asbestos.
NAD - no asbestos detected, NA - not applicable, PS – Positive Stop, SF - square feet, LF – linear feet